Floor 0 Structural & Finishes Report

1. Floor Summary

Level: 0 | **Floor Height:** 3.00 m | **Columns at Level:** 12

2. Column Schedule for Level

ID	Location (x,y)	Size (mm)	Load (kN)	Main Steel	Stirrups
C1_L0	(0.00, 0.00)	300x450	185.2	8-16#	8# @ 150 c/c
C2_L0	(0.00, 4.50)	300x450	311.2	8-16#	8# @ 150 c/c
C3_L0	(0.00, 9.00)	300x450	185.2	8-16#	8# @ 150 c/c
C4_L0	(4.00, 0.00)	300x450	305.2	8-16#	8# @ 150 c/c
C5_L0	(4.00, 4.50)	400x600	505.5	10-16#	8# @ 150 c/c
C6_L0	(4.00, 9.00)	300x450	305.2	8-16#	8# @ 150 c/c
C7_L0	(8.00, 0.00)	300x450	305.2	8-16#	8# @ 150 c/c
C8_L0	(8.00, 4.50)	400x600	505.5	10-16#	8# @ 150 c/c
C9_L0	(8.00, 9.00)	300x450	305.2	8-16#	8# @ 150 c/c
C10_L0	(12.00, 0.00)	300x450	185.2	8-16#	8# @ 150 c/c
C11_L0	(12.00, 4.50)	300x450	311.2	8-16#	8# @ 150 c/c
C12_L0	(12.00, 9.00)	300x450	185.2	8-16#	8# @ 150 c/c

3. Beam Schedule for Level

ID	Size	Top Steel	Bottom Steel	Stirrups
B_H_1	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_2	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_3	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_4	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_5	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_6	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_7	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_8	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_H_9	230x350	2-12#	5-20#	2L-8# @ 230 c/c
B_V_10	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_11	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_12	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_13	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_14	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_15	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_16	230x400	2-12#	5-20#	2L-8# @ 230 c/c
B_V_17	230x400	2-12#	5-20#	2L-8# @ 230 c/c

4. Slab Schedule for Level

ID	Thickness (mm)	Main Steel	Distribution Steel
S1	185	10# @ 300 c/c	10# @ 300 c/c
S2	185	10# @ 300 c/c	10# @ 300 c/c
S3	185	10# @ 300 c/c	10# @ 300 c/c
S4	185	10# @ 300 c/c	10# @ 300 c/c
S5	185	10# @ 300 c/c	10# @ 300 c/c
S6	185	10# @ 300 c/c	10# @ 300 c/c

5. Floor 0 Masonry Brickwork Schedule (IS 1077, IS 2250)

Wall ID	Span / Cols	Len (m)	Ht (m)	Thk	Gross (m³)	Bricks (Nos)	Brick Vol	Wet Mor	Dry Mor	Cem Bags	Cem (kg)	Sand (T)	Water (L)
W_H1	C1_L0→C4_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H2	C4_L0→C7_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H3	C7_L0→C10_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H4	C2_L0→C5_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H5	C5_L0→C8_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H6	C8_L0→C11_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H7	C3_L0→C6_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H8	C6_L0→C9_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_H9	C9_L0→C12_L0	4.00	2.48	200mm	1.98	495	1.61	0.372	0.494	3	142.4	0.63	71
W_V10	C1_L0→C2_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V11	C2_L0→C3_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V12	C4_L0→C5_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V13	C5_L0→C6_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V14	C7_L0→C8_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V15	C8_L0→C9_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V16	C10_L0→C11_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
W_V17	C11_L0→C12_L0	4.50	2.48	200mm	2.23	557	1.81	0.418	0.556	4	160.0	0.71	80
TOTAL	All Walls	-	-	-	35.64	8,911	28.95	6.69	8.90	52	2,562	11.39	1,281

6. Floor 0 Plastering Schedule (IS 1661, IS 2402)

Surface ID	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem (Bags)	Cem (kg)	Sand (T)	Water (L)
W_H1_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H1_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_H2_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H2_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_H3_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H3_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_H4	Int Part (2-Face 12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H5	Int Part (2-Face 12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33

Surface ID	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem (Bags)	Cem (kg)	Sand (T)	Water (L)
W_H6	Int Part (2-Face 12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H7_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H7_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_H8_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H8_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_H9_EXT	Ext Render (15mm 1:4)	9.9	15	1:4	0.148	0.198	2	56.9	0.25	28
W_H9_INT	Int Wall (12mm 1:6)	9.9	12	1:6	0.119	0.158	1	32.5	0.22	16
W_V10_EXT	Ext Render (15mm 1:4)	11.1	15	1:4	0.167	0.222	2	64.0	0.28	32
W_V10_INT	Int Wall (12mm 1:6)	11.1	12	1:6	0.134	0.178	1	36.6	0.24	18
W_V11_EXT	Ext Render (15mm 1:4)	11.1	15	1:4	0.167	0.222	2	64.0	0.28	32
W_V11_INT	Int Wall (12mm 1:6)	11.1	12	1:6	0.134	0.178	1	36.6	0.24	18
W_V12	Int Part (2-Face 12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V13	Int Part (2-Face 12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V14	Int Part (2-Face 12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V15	Int Part (2-Face 12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V16_EXT	Ext Render (15mm 1:4)	11.1	15	1:4	0.167	0.222	2	64.0	0.28	32
W_V16_INT	Int Wall (12mm 1:6)	11.1	12	1:6	0.134	0.178	1	36.6	0.24	18
W_V17_EXT	Ext Render (15mm 1:4)	11.1	15	1:4	0.167	0.222	2	64.0	0.28	32
W_V17_INT	Int Wall (12mm 1:6)	11.1	12	1:6	0.134	0.178	1	36.6	0.24	18
Ceiling Soffit	Slab Bottom (6mm 1:3)	108.0	6	1:3	0.648	0.862	7	310.3	1.03	155
TOTAL	All Plaster Surfaces	464.4	-	-	5.237	6.965	35	1,736	9.21	868

7. Floor 0 Painting & Finishes Schedule (NBC 2016)

Surface ID	Location & Specification	Finish Area (m²)	Primer 1-Ct (L)	Putty 2-Ct (kg)	Int Emulsion 2-Ct (L)	Ext Weather 2-Ct (L)
W_H1_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H1_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_H2_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H2_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_H3_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H3_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_H4	Internal Partition Emulsion	19.8	2.5	29.7	3.3	—
W_H5	Internal Partition Emulsion	19.8	2.5	29.7	3.3	—
W_H6	Internal Partition Emulsion	19.8	2.5	29.7	3.3	—
W_H7_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H7_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_H8_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H8_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_H9_EXT	External Weather Guard	9.9	1.2	—	—	2.0
W_H9_INT	Internal Acrylic Emulsion	9.9	1.2	14.9	1.7	—
W_V10_EXT	External Weather Guard	11.1	1.4	—	—	2.2

Surface ID	Location & Specification	Finish Area (m²)	Primer 1-Ct (L)	Putty 2-Ct (kg)	Int Emulsion 2-Ct (L)	Ext Weather 2-Ct (L)
W_V10_INT	Internal Acrylic Emulsion	11.1	1.4	16.7	1.9	—
W_V11_EXT	External Weather Guard	11.1	1.4	—	—	2.2
W_V11_INT	Internal Acrylic Emulsion	11.1	1.4	16.7	1.9	—
W_V12	Internal Partition Emulsion	22.3	2.8	33.4	3.7	—
W_V13	Internal Partition Emulsion	22.3	2.8	33.4	3.7	—
W_V14	Internal Partition Emulsion	22.3	2.8	33.4	3.7	—
W_V15	Internal Partition Emulsion	22.3	2.8	33.4	3.7	—
W_V16_EXT	External Weather Guard	11.1	1.4	—	—	2.2
W_V16_INT	Internal Acrylic Emulsion	11.1	1.4	16.7	1.9	—
W_V17_EXT	External Weather Guard	11.1	1.4	—	—	2.2
W_V17_INT	Internal Acrylic Emulsion	11.1	1.4	16.7	1.9	—
Ceiling Soffit	Slab Underside (White Emulsion)	108.0	13.5	162.0	18.0	—
TOTAL	All Surfaces (Walls + Ceilings)	464.4	58.0	540.7	60.1	20.8

8. Floor 0 Masonry & Finishes Material Takeoff

Item / Material Description	Specification / Mix Proportion	Building Total	Unit	IS Standard
Total Wall Gross Volume	L × t × Hv (clear story height)	35.64	m³	IS 1905:1987
Clay Modular Building Bricks	Standard modular 20×20×10 cm	8,911	Nos	IS 1077:1992
Net Solid Brickwork Volume	Actual brick body volume (excl. mortar)	28.95	m³	IS 1077:1992
Wet Brickwork Mortar Volume	Gross Wall Volume – Solid Brick Vol	6.69	m³	IS 2250:1981
Dry Brickwork Mortar Volume	Wet Volume × 1.33 dry factor	8.90	m³	IS 2250:1981
Brickwork Cement	1:4 Mix Proportion (OPC / PPC)	52 (2,562 kg)	Bags (50kg)	IS 269:2015
Brickwork Sand	Coarse sand, dry density 1600 kg/m³	11.39	Tonnes	IS 383 Zone II
Brickwork Water	Water:Cement ratio = 0.50	1,281	Litres	IS 456 Cl 5.4
Wall Plastering Surface Area	Internal (12mm 1:6) + External (15mm 1:4)	356.4	m²	IS 1200 Pt 12
Ceiling Soffit Plaster Area	Soffit bottom of slabs (6mm 1:3 mix)	108.0	m²	IS 1661:1972
Total Plaster Surface Area	Combined wall + ceiling surface	464.4	m²	IS 1200 Pt 12
Plastering Cement	Combined wall & ceiling plaster	35 (1,736 kg)	Bags (50kg)	IS 1661 / IS 2402
Plastering Sand	Clean plaster sand (Zone III/IV)	9.21	Tonnes	IS 383:2016
Plastering Water	Water:Cement ratio = 0.50	868	Litres	IS 456 Cl 5.4
Surface Primer	Water-thinnable primer @ 8 m²/L (1 coat)	58.1	Litres	NBC 2016 SP7
Polymer Wall Putty	2 coats (1–2 mm) @ 1.5 kg/m²	919.4	kg	NBC 2016 SP7
Interior Acrylic Emulsion	2 coats (30–40 microns) @ 12 m²/L	60.1	Litres	NBC 2016 SP7
Exterior Weather Emulsion	2 coats (40–60 microns) @ 10 m²/L	20.8	Litres	NBC 2016 SP7
GRAND TOTAL CEMENT (Mortar + Plaster)	All masonry + plastering works combined	87 bags (4,298 kg)	Bags	IS 269:2015
GRAND TOTAL SAND (Mortar + Plaster)	All masonry + plastering sand combined	20.60	Tonnes	IS 383:2016
GRAND TOTAL WATER (Mortar + Plaster)	All masonry + plastering water combined	2,149	Litres	IS 456 Cl 5.4