Floor 0 Structural & Finishes Report

1. Floor Summary

Level: 0 | **Floor Height:** 3.00 m | **Columns at Level:** 12

2. Column Schedule for Level

ID	Location (x,y)	Size (mm)	Load (kN)	Main Steel	Stirrups
C0_L0	(0.00, 0.00)	300x300	0.0	-	-
C1_L0	(3.30, 0.00)	300x300	0.0	-	-
C2_L0	(6.60, 0.00)	300x300	0.0	-	-
C3_L0	(9.90, 0.00)	300x300	0.0	-	-
C4_L0	(0.00, 4.00)	300x300	0.0	-	-
C5_L0	(3.30, 4.00)	300x300	0.0	-	-
C6_L0	(6.60, 4.00)	300x300	0.0	-	-
C7_L0	(9.90, 4.00)	300x300	0.0	-	-
C8_L0	(0.00, 8.00)	300x300	0.0	-	-
C9_L0	(3.30, 8.00)	300x300	0.0	-	-
C10_L0	(6.60, 8.00)	300x300	0.0	-	-
C11_L0	(9.90, 8.00)	300x300	0.0	-	-

3. Beam Schedule for Level

ID	Size	Top Steel	Bottom Steel	Stirrups
N/A	-	-	-	-

4. Slab Schedule for Level

ID	Thickness (mm)	Main Steel	Distribution Steel
N/A	-	-	-

5. Floor 0 Masonry Brickwork Schedule (IS 1077, IS 2250)

Wall ID	Fl	Span / Cols	Len (m)	Ht (m)	Thk (mm)	Gross Vol (m³)	Bricks (Nos)	Brick Vol (m³)	Wet Mortar (m³)	Dry Mortar (m³)	Cem Bags	Cem (kg)	Sand (T)	Water (L)
W1_F0	F0	Bay	10.00	2.48	230	5.693	1,424	4.627	1.066	1.418	9	408.3	1.815	204
W2_F0	F0	Bay	12.00	2.48	230	6.831	1,708	5.549	1.282	1.705	10	490.9	2.182	245
TOTAL	**1Fl**	**All Walls**	**-**	**-**	**-**	**12.52**	**3,132**	**10.18**	**2.35**	**3.12**	**18**	**899**	**4.00**	**450**

6. Floor 0 Plastering Schedule (IS 1661, IS 2402)

Surface ID	Fl	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem Bags	Cem (kg)	Sand (T)	Water (L)
W1_EXT_F0	F0	Ext Render (15mm 1:4)	24.75	15	1:4	0.371	0.494	3	142.2	0.632	71
W1_INT_F0	F0	Int Wall (12mm 1:6)	24.75	12	1:6	0.297	0.395	2	81.3	0.542	41
W2_EXT_F0	F0	Ext Render (15mm 1:4)	29.70	15	1:4	0.446	0.593	4	170.6	0.758	85

Surface ID	Fl	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem Bags	Cem (kg)	Sand (T)	Water (L)
W2_INT_F0	F0	Int Wall (12mm 1:6)	29.70	12	1:6	0.356	0.474	2	97.5	0.650	49
Ceil_F0	F0	Slab Soffit (6mm 1:3)	120.00	6	1:3	0.720	0.958	7	344.7	1.149	172
TOTAL	**1Fl**	**All Plaster Surfaces**	**228.9**	**-**	**-**	**2.190**	**2.913**	**17**	**836**	**3.73**	**418**

7. Floor 0 Painting & Finishes Schedule (NBC 2016)

Surface ID	Fl	Location & Specification	Area (m²)	Primer 1-Ct (L)	Putty 2-Ct (kg)	Int Em 2-Ct (L)	Ext Guard 2-Ct (L)
W1_EXT_F0	F0	External Weather Guard	24.75	3.09	—	—	4.95
W1_INT_F0	F0	Int Acrylic Emulsion	24.75	3.09	74.25	4.12	—
W2_EXT_F0	F0	External Weather Guard	29.70	3.71	—	—	5.94
W2_INT_F0	F0	Int Acrylic Emulsion	29.70	3.71	89.10	4.95	—
Ceil_F0	F0	Slab Soffit (White Emulsion)	120.00	15.00	360.00	20.00	—
TOTAL	**1Fl**	**All Surfaces (Walls + Ceilings)**	**228.9**	**28.6**	**523.4**	**29.1**	**10.9**

8. Floor 0 Masonry & Finishes Material Takeoff

Item / Material Description	Specification / Mix Proportion	Building Total	Unit	IS Standard
Total Wall Gross Volume	L × t × Hv (clear storey height)	12.52	m³	IS 1905:1987
Clay Modular Building Bricks	Standard modular 20×20×10 cm	3,132	Nos	IS 1077:1992
Net Solid Brickwork Volume	Actual brick body vol. (excl. mortar)	10.18	m³	IS 1077:1992
Wet Brickwork Mortar Volume	Gross Wall Vol – Solid Brick Vol	2.35	m³	IS 2250:1981
Dry Brickwork Mortar Volume	Wet Volume × 1.33 dry factor	3.12	m³	IS 2250:1981
Brickwork Cement	1:4 Mix Proportion (OPC/PPC)	18 (899 kg)	Bags 50kg	IS 269:2015
Brickwork Sand	Coarse sand, dry density 1600 kg/m³	4.00	Tonnes	IS 383 Zone II
Brickwork Water	Water:Cement ratio = 0.50	450	Litres	IS 456 Cl 5.4
Wall Plaster Area	Int (12mm 1:6) + Ext (15mm 1:4)	108.9	m²	IS 1200 Pt 12
Ceiling Soffit Plaster Area	Soffit of slabs (6mm 1:3 mix)	120.0	m²	IS 1661:1972
Total Plaster Surface Area	Combined wall + ceiling surface	228.9	m²	IS 1200 Pt 12
Plastering Cement	Combined wall & ceiling plaster	17 (836 kg)	Bags 50kg	IS 1661/IS 2402
Plastering Sand	Clean plaster sand (Zone III/IV)	3.73	Tonnes	IS 383:2016
Plastering Water	W:C = 0.50	418	Litres	IS 456 Cl 5.4
Surface Primer	1 coat @ 8 m²/L	28.6	Litres	NBC 2016 SP7
Polymer Wall Putty	2 coats @ 1.5 kg/m²	523.4	kg	NBC 2016 SP7
Interior Acrylic Emulsion	2 coats @ 12 m²/L	29.1	Litres	NBC 2016 SP7
Exterior Weather Emulsion	2 coats @ 10 m²/L	10.9	Litres	NBC 2016 SP7
GRAND TOTAL CEMENT (Mortar+Plaster)	**All masonry + plastering combined**	**35 bags (1,736 kg)**	**Bags**	**IS 269:2015**
GRAND TOTAL SAND (Mortar+Plaster)	**All masonry + plastering sand**	**7.73**	**Tonnes**	**IS 383:2016**
GRAND TOTAL WATER (Mortar+Plaster)	**All masonry + plastering water**	**868**	**Litres**	**IS 456 Cl 5.4**