Test Brickwork Table

Wall ID	Span / Cols	Len (m)	Ht (m)	Thk	Gross (m³)	Bricks	Brick Vol	Wet Mor	Dry Mor	Cem Bags	Cem (kg)	Sand (T)	Water (L)
W_H1	C1_L0→C4_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H2	C4_L0→C7_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H3	C7_L0→C10_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H4	C2_L0→C5_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H5	C5_L0→C8_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H6	C8_L0→C11_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H7	C3_L0→C6_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H8	C6_L0→C9_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_H9	C9_L0→C12_L0	4.00	2.48	200mm	3.96	990	3.22	0.743	0.989	6	284.8	1.27	142
W_V10	C1_L0→C2_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V11	C2_L0→C3_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V12	C4_L0→C5_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V13	C5_L0→C6_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V14	C7_L0→C8_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V15	C8_L0→C9_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V16	C10_L0→C11_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
W_V17	C11_L0→C12_L0	4.50	2.48	200mm	4.46	1,114	3.62	0.836	1.111	7	320.1	1.42	160
TOTAL	All Walls	-	-	-	71.28	17,822	57.90	13.38	17.79	103	5,124	22.77	2,562

Test Plaster Table

Surface ID	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem (Bags)	Cem (kg)	Sand (T)	Water (L)
W_H1_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H1_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H2_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H2_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H3_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H3_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H4	Int Part (2-Face 12mm 1:6)	39.6	12	1:6	0.475	0.632	3	130.0	0.87	65
W_H5	Int Part (2-Face 12mm 1:6)	39.6	12	1:6	0.475	0.632	3	130.0	0.87	65
W_H6	Int Part (2-Face 12mm 1:6)	39.6	12	1:6	0.475	0.632	3	130.0	0.87	65
W_H7_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H7_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H8_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H8_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_H9_EXT	Ext Render (15mm 1:4)	19.8	15	1:4	0.297	0.395	3	113.8	0.51	57
W_H9_INT	Int Wall (12mm 1:6)	19.8	12	1:6	0.238	0.316	2	65.0	0.43	33
W_V10_EXT	Ext Render (15mm 1:4)	22.3	15	1:4	0.334	0.444	3	128.0	0.57	64
W_V10_INT	Int Wall (12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V11_EXT	Ext Render (15mm 1:4)	22.3	15	1:4	0.334	0.444	3	128.0	0.57	64

Surface ID	Location & Mix Spec	Area (m²)	Thk (mm)	Mix	Wet Vol (m³)	Dry Vol (m³)	Cem (Bags)	Cem (kg)	Sand (T)	Water (L)
W_V11_INT	Int Wall (12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V12	Int Part (2-Face 12mm 1:6)	44.6	12	1:6	0.535	0.711	3	146.3	0.98	73
W_V13	Int Part (2-Face 12mm 1:6)	44.6	12	1:6	0.535	0.711	3	146.3	0.98	73
W_V14	Int Part (2-Face 12mm 1:6)	44.6	12	1:6	0.535	0.711	3	146.3	0.98	73
W_V15	Int Part (2-Face 12mm 1:6)	44.6	12	1:6	0.535	0.711	3	146.3	0.98	73
W_V16_EXT	Ext Render (15mm 1:4)	22.3	15	1:4	0.334	0.444	3	128.0	0.57	64
W_V16_INT	Int Wall (12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
W_V17_EXT	Ext Render (15mm 1:4)	22.3	15	1:4	0.334	0.444	3	128.0	0.57	64
W_V17_INT	Int Wall (12mm 1:6)	22.3	12	1:6	0.267	0.356	2	73.1	0.49	37
Ceiling Soffit	Slab Bottom (6mm 1:3)	216.0	6	1:3	1.296	1.724	13	620.5	2.07	310
TOTAL	All Plaster Surfaces	928.8	-	-	10.473	13.929	70	3,473	18.43	1,736

Test Paint Table

Surface ID	Location & Specification	Finish Area (m²)	Primer 1-Ct (L)	Putty 2-Ct (kg)	Int Emulsion 2-Ct (L)	Ext Weather 2-Ct (L)
W_H1_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H1_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_H2_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H2_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_H3_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H3_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_H4	Internal Partition Emulsion	39.6	5.0	59.4	6.6	—
W_H5	Internal Partition Emulsion	39.6	5.0	59.4	6.6	—
W_H6	Internal Partition Emulsion	39.6	5.0	59.4	6.6	—
W_H7_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H7_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_H8_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H8_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_H9_EXT	External Weather Guard	19.8	2.5	—	—	4.0
W_H9_INT	Internal Acrylic Emulsion	19.8	2.5	29.7	3.3	—
W_V10_EXT	External Weather Guard	22.3	2.8	—	—	4.5
W_V10_INT	Internal Acrylic Emulsion	22.3	2.8	33.4	3.7	—
W_V11_EXT	External Weather Guard	22.3	2.8	—	—	4.5
W_V11_INT	Internal Acrylic Emulsion	22.3	2.8	33.4	3.7	—
W_V12	Internal Partition Emulsion	44.6	5.6	66.8	7.4	—
W_V13	Internal Partition Emulsion	44.6	5.6	66.8	7.4	—
W_V14	Internal Partition Emulsion	44.6	5.6	66.8	7.4	—
W_V15	Internal Partition Emulsion	44.6	5.6	66.8	7.4	—
W_V16_EXT	External Weather Guard	22.3	2.8	—	—	4.5
W_V16_INT	Internal Acrylic Emulsion	22.3	2.8	33.4	3.7	—
W_V17_EXT	External Weather Guard	22.3	2.8	—	—	4.5

Surface ID	Location & Specification	Finish Area (m²)	Primer 1-Ct (L)	Putty 2-Ct (kg)	Int Emulsion 2-Ct (L)	Ext Weather 2-Ct (L)
W_V17_INT	Internal Acrylic Emulsion	22.3	2.8	33.4	3.7	—
Ceiling Soffit	Slab Underside (White Emulsion)	216.0	27.0	324.0	36.0	—
TOTAL	All Surfaces (Walls + Ceilings)	928.8	116.1	1,081.4	120.1	41.6